

QUESTIONS AND ANSWERS

REQUEST FOR PROPOSAL

PROJECT NO. 14-10

PROJECT TITLE: Missouri City Athletic Fields

Date: December 10, 2013

To: Prospective Respondents

From: Procurement Operations Department, Houston Community College

Subject: Questions and Answers Request for Proposals, HCC **Project No. 14-10**

- 1) Could you please clarify the scope of the asphalt work to be done by the general contractor and what will be done by HCC, the note on detail 11/L3.01 is vague.

Answer: The excavation and base and sub-base preparations are to be provided by the General Contractor. The Asphalt will placed by a coordinated source through Houston Community College.

- 2) Are the moveable bollards to be included in the bid? They show on L2.01 but the detail 5/L4.01 shows to be deleted.

Answer: Movable bollards are included in the scope of work, See attached sheet L4.01.

- 3) What is the thickness of the asphalt, on sheet C13.00 one detail says 2" and one detail says 2-1/2".

Answer: Provide 2" Asphalt Pavement.

- 4) Where is the curb that is noted as alternate # 1 shown on C13.00.

Answer: Alternate #1 is not used, all curbs are to be monolithic curb and gutter.

- 5) Does the lime stabilization extend under the curb and gutter.

Answer: Yes.

- 6) Does the curb and gutter go at the drive and parking lot or just at the drive with the parking lot getting a curb on top of the asphalt.

Answer: Curb and gutter will go in the drive and parking lot.

- 7) Will there be any aluminum bleachers?

Answer: Yes, aluminum bleachers are required and specified.